OFFICE
GROUND FLOOR PLAN
COVERED AREA=97.00 SQ.M.

TERRACE FLOOR PLAN

TYP. BRICK FOUNDATION
230TH WALL SEC.1-1

# PLINTH BAND

A T8 @200C/C
B T10 @200C/C

ROOF SLAB PLAN
(RCC SLAB THICKNESS 110 MM)

FRONT ELEVATION

REAR ELEVATION

SECTION-AA

| DOOR WINDOW SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| S.N. | TYPE | OPENINGS | SILL | LINTEL | LOCATION | REMARK |
| DOORS | | | | | | |
| 1. | D1 | 1800 X 2100 | - | 2100 | ENT. LOBBY | FLUSH DOOR |
| 2. | D2 | 900 X 2100 | - | 2100 | MAIN DOOR TOI | FLUSH DOOR |
| 3. | D3 | 800 X 2100 | - | 2100 | TOILET | P.V.C DOOR |
| WINDOWS | | | | | | |
| 1. | W1 | 1800 X 1200 | 900 | 2100 | OFFICE BLOCK | STEEL GL |
| 2. | W2 | 650 X 1200 | 900 | 2100 | WAITING AREA | STEEL GL |
| 3. | V1 | 600 X 600 | 1500 | 2100 | TOILET | STEEL GL |

## TENDER DRAWING

PROJECT :-

CONSTRUCTION OF FCI PRE **ENGINEERED** GODOWNS IN AALO (ARUNACHAL PRADESH)

CLIENT :-
HINDUSTAN PREFAB. LTD.
JANGPURA, NEW DELHI

DRG TITLE :-

PLAN, ELEVATION & SECTION OF OFFICE BLOCK

DRAWING NO:- AR-O-01

SCALE :-

DATE-1.12.2017

**DRAWN BY:**

**CHECKED BY:**

ASSOCIATES CONSULTANTS :-


Buildcon Solutions
HEAD OFFICE :- L-11,SARITA VIHAR,
NEW DELHI-76
TELE FAX :- 011 - 40506870
EMAIL-buildconsolutions@gmail.com