CONSTRUCTION OF 1670 MT CAPACITY FCI GODOWN AT AALO.A.P STATE

Estimate (Based on CPWD,Schedule of rates 2016 Delhi)

BOQ FOR EARTH WORK (CUTTING) **ANNEXURE IX**

S NO.	Description	Qty	Unit	Rate(Rs)	Amount (Rs)	.DSR 2016 No
3(ii)a	**SCHEDULE ITEMS**					
1	Earth work in excavation by mechanical means (Hydralic excavator/ manual means)over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m; disposed earth to be levelled and neatly dressed All kinds of soil	1930.00	cum	125.95	243083.50	2.6.1
	TOTAL				**243083.50**	