NOTE:—CANOPY LOCATION TO BE CONFIRMED BY THE CUSTOMER FOR COLUMN REACTION READ SEPERATE SHEET

ANCHOR BOLT SETTING

ANCHOR BOLT SCHEDULE -- BOLTS BY:-

SYMBOL	QUANTITY	DIAMETER	L	A	B	C	D	PIECE MARK
	-	16	410	100	75	325	75	-
	-	20	525	120	100	435	100	-
	96	24	665	150	100	565	100	-
	-	32	1000	200	125	875	125	-
	-	36	1350	200	150	1300	200	-
	-	40	1650	250	150	1600	200	-
	-	50	1650	300	150	1500	200	-

SAMPLE DETAIL OF MINIMUM PEDESTAL REQUIREMENT

ANCHOR BOLT DETIAL PLAN

NOTES :-

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN.
2. WRITTEN DIMENSIONS ARE TO BE FOLLOWED.
3. ANY DISCREPANCY IN THE DRAWINGS SHALL BE BROUGHT TO THE NOTICE OF THE ARCHITECT.
4. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH OTHER RELEVANT DRAWINGS
5. ALL LEVELS INDICATED ARE FINISHED FLOOR LEVELS(UNLESS MENTIONED OTERWISE.
6. FOR ELECTRICAL /PLUMBING REFER DETAIL DRAWINGS.
7. ALL STEEL WORKS HAVE ONE COAT OF STEEL PRIMER & TWO COAT OF SYNTHETIC ENAMEL PAINT
8.

TENDER DRAWING

PROJECT :-

CONSTRUCTION OF FCI PRE **ENGINEERED** GODOWNS IN AALO (ARUNACHAL PRADESH)

CLIENT :-
HINDUSTAN PREFAB. LTD.
JANGPURA, NEW DELHI

DRG TITLE :-

ANCHOR BOLT SETTING PLAN

DRAWING NO:- ST-G-03

SCALE :- DATE-1.12.2017

DRAWN BY: CHECKED BY:

ASSOCIATES CONSULTANTS :-

Buildcon Solutions
HEAD OFFICE :- L-11,SARITA VIHAR,
NEW DELHI-76
TELE FAX :- 011 - 40506870
EMAIL-buildconsolutions@gmail.com