CONSTRUCTION OF 1670 MT CAPACITY FCI GODOWN AT AALO.A.P STATE						
Estimate (Based on CPWD,Schedule of rates 2016 Delhi)						
BOQ FOR ROAD WORK						ANNEXURE VIII
SL. NO.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	Amount (Rs.)	DSR 2016 NO
1	2	3	4	5	6	7
3(i)a	SCHEDULE ITEMS					
	SUB HEAD - II EARTH WORK					
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tone capacity after excavating earth to an average of 22.5 cm. depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth lead upto 50 metres.	1,842.50	sqm	90.10	166,009.25	16.1
2	Providing and laying in position cement concrete of specified grade all work upto plinth level					
	1:4:8 (1 cement:4 coarse sand:8 graded stone aggregate)	239.53	cum	4,478.15	1,072,651.26	4.1.8
3	Providing and laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and taming complete	479.05	cum	5,503.80	2,636,595.39	16.42
4	Providing and fixing pre moulded joint filler in expansion joints	2,976.00	per cm depth per cm width per m length	2.20	6,547.20	16.45
5	Providing and laying in position bitumen sealing compound for expansion joints	1,045.50	depth per cm width per m length	2.20	2,300.10	16.46
	TOTAL SCHEDULE ITEMS (IN Rs.)				**3,884,103.20**	