CONSTRUCTION OF 1670 MT CAPACITY FCI GODOWN AT AALO.A.P STATE						
BOQ FOR FOR WEIGH BRIDGE AND CABIN					ANNEXURE XV	
A						
SL. NO.	**DESCRIPTION OF ITEM**	**Qty.**	**UNIT**	**Rate (Rs)**	**Amount (Rs.)**	**MR**
5(i)a	and Commisioning of Electronic Lorrey Weigh Bridge at Site Comprising of Platform, Structures, load-cells, Digital Weight Indicator Printer compatible with PC, PC with alpha-numeric key board, interconnecting cables, Junction box, UPS, Stabilizer, 17" LCD Colour Monitor, Mouse, Jumbo display unit for 40 MT, 9mx3m/9mx3m /16mx3m platform size pitless/Shallow pit type weigh-bridge, including , excise duty and all other taxes Sales Tax / VAT ,octroi, transportation charges and stamping charges etc complete as per Technical specifications including defects liabilty period and maintaince at site charges for 2 years complete and all civil works complete for construction of Weigh Bridge foundation as per manufacturers instructions manual complete .					
		1	each	1200000.00	1200000.00	
1b	Construction of Weigh Bridge Room including excavation, load bearing structure,finishing work including all elevtrical works complete as per drawings	15	sqm	20000.00	300000.00	
	TOTAL MARKET RATE ITEM IN RS				**1500000.0**	