CONSTRUCTION OF 1670 MT CAPACITY FCI GODOWN AT AALO , A.P STATE						
BOQ FOR BOREWELL AND RECHARGE PIT ANNEXURE XIV						
A						
SL. NO	**DESCRIPTION OF ITEM**	**Qty.**	**UNIT**	**Rate**	**Amount (Rs.)**	**MR**
1a	Supply , Installation testing and commisioning of Borewell 300 mm dia 75 mts depth with 50% PVC medium well casing pipes and 50% PVC Slotted pipes 200 mm dia 60 mts each and GI pipe 40mm dia 80 mts length including development of Bore well and with 3 HP motor and starter with electrical panel and wiring complete	1	each	700000.00	700000.00	
1b	Providing 2 m dia 2.m deep recharge pit with sand , gravels etc and 100mm dia 10 mts PVC pipe with boring with brick masonary walls RCC slab over it with Manhole cover etc					
		1	each	100000.00	100000.00	
	TOTAL				**800000.0**	