TIFFIN ROOM
GROUND FLOOR PLAN
COVERED AREA=34.00 SQ.M.

TYP. BRICK FOUNDATION
230TH WALL SEC.1-1

TERRACE PLAN

PLINTH BAND

SECTION-AA

A T8 @200C/C
B T10 @200C/C

ROOF SLAB PLAN
(RCC SLAB THICKNESS 110 MM)

FRONT ELEVATION

REAR ELEVATION

DOOR WINDOW SCHEDULE

S.N.	TYPE	OPENINGS	SILL	LINTEL	LOCATION	REMARK
DOORS						
1.	D1	1500 X 2100	-	2100	ENT. LOBBY	FLUSH DOOR
WINDOWS						
1.	W1	1500 X 1200	900	2100	OFFICE	STEEL GL
6.	V1	600 X 600	1500	2100	TOILET	STEEL GL

TENDER DRAWING

PROJECT :-

CONSTRUCTION OF FCI PRE **ENGINEERED** GODOWNS IN AALO (ARUNACHAL PRADESH)

CLIENT :-
HINDUSTAN PREFAB. LTD.
JANGPURA, NEW DELHI

DRG TITLE :-

PLAN, ELEVATION & SECTION DWG. OF TIFFIN ROOM

DRAWING NO:- AR-T-01

SCALE :- DATE-01.12.2017

DRAWN BY: **CHECKED BY:**

ASSOCIATES CONSULTANTS :-

Buildcon Solutions
HEAD OFFICE :- L-11,SARITA VIHAR,
NEW DELHI-76
TELE FAX :- 011 - 40506870
EMAIL-buildconsolutions@gmail.com