CONSTRUCTION OF 1670 MT CAPACITY FCI GODOWN AT AALO.A.P STATE

(Based on CPWD,Schedule of rates 2016 Delhi)

BOQ FOR CYCLE SHED **ANNEXURE VI**

SL. NO.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE(Rs)	Amount (Rs.)	DSR2016 NO
1	2	3.00	4	5.00	6.00	7
2(iii)a	**SCHEDULE ITEMS**					
	CIVIL WORKS					
1	Earth work in experience by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. i) All kinds of soil.	12.15	cum	166.40	2,021.76	2.8.1
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in wateriing, lead upto to 50m and lift upto 1.5m	12.15	cum	125.75	1,527.86	2.25
3	Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete.	1.02	cum	917.75	936.11	2.27
4	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground leveland removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	0.20	100sqm	7.20	1.44	2.31
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	2.70	cum	4,478.15	12,091.01	4.1.8
6	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 12.5mm nominal size).	3.45	sqm	263.10	907.70	4.10
7	Applying a coat of residual petroleum bitumen of penetration 80/100 of approved quality using 1.7kg per square meter on damp proof course after cleaning the surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil.	3.45	sqm	91.90	317.06	4.13
8	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with fine sand	9.00	sqm	450.35	4,053.15	4.17
9	Centring and shuttering including strutting, propping etc. and removal of form for:removal of form for:					
	Suspended floors, roofs, landings, balconies and access platform	22.00	sqm	422.30	9,290.60	5.9.3
10	Shelves		sqm	422.30		5.9.4
11	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete Above plinth level. Thermo-Mechanically Treated bars.	279.00	Kg	56.60	15,791.40	5.22.6 A
12	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	3.10	cum	7,390.80	22,911.48	5.33A

CONSTRUCTION OF 1670 MT CAPACITY FCI GODOWN AT AALO.A.P STATE

(Based on CPWD,Schedule of rates 2016 Delhi)

BOQ FOR CYCLE SHED **ANNEXURE VI**

SL. NO.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE(Rs)	Amount (Rs.)	DSR2016 NO
1	2	3.00	4	5.00	6.00	7
2(iii)a	**SCHEDULE ITEMS**					
	CIVIL WORKS					
13	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	7.65	cum	4,751.65	36,350.12	6.1.2
14	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement: 6 coarse sand)	6.50	cum	5,582.85	36,288.53	6.4.2
15	52 mm thick cement concrete flooring with concrete hardener topping under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume .hardening compound is mixed @ 2 liter per 50kg of cement or as per manufacturers specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete.	15.75	sqm	555.25	8,745.19	11.4
16	Cement plaster skirting (upto 30 cm height) with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement. 18 mm thick.	0.70	sqm	350.05	245.04	11.6.1
17	12mm cement plaster of mix: 1:6 (1 cement : 6fine sand)	24.68	sqm	160.35	3,956.64	13.1.2
18	15mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)	24.68	sqm	200.25	4,941.17	13.2.1
19	White washing with lime to give an even shade New work(three or more coats)	24.68	sqm	17.25	425.64	13.37
20	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm).	24.68	Sqm	58.80	1,450.89	13.44.1
21	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm. of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300mm height including cleaning the surface before treatment. (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement :5 coarse sand) admixed with water proofing compound					

CONSTRUCTION OF 1670 MT CAPACITY FCI GODOWN AT AALO.A.P STATE

(Based on CPWD,Schedule of rates 2016 Delhi)

BOQ FOR CYCLE SHED **ANNEXURE VI**

SL. NO.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE(Rs)	Amount (Rs.)	DSR2016 NO
1	2	3.00	4	5.00	6.00	7
2(iii)a	**SCHEDULE ITEMS**					
	CIVIL WORKS					
	(c) After two days of proper curing applying a second coat of cement slurry using 2.75kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement :4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. All above operations to be done in order and as directed and specified by the Engineer-in-Charge : With average thickness of 120mm and minimum thickness at khurra as 65 mm	15.20	sqm	1,034.35	15,722.12	22.7
	TOTAL SCHEDULE ITEMS (IN Rs.) (A)				**177,974.88**	
2(iii)b	**SCHEDULE ITEMS**					
	INTERNAL ELECTRICAL WORKS					
	POINT AND SUB-MAIN WIRING					
1	Point wiring in steel conduit, with modular type switch Wiring					
	Group-A	4	Point	659.00	2,636.00	1.1.1
2	**Circuit/ submain wiring in PVC conduit :**					
	Wiring for circuit/ submain wiring alongwith earh wire with the					
	2X4 Sq. mm+1x4 Sq. mm earth Wire	5	M	237.00	1,185.00	1.7.2
	2x6Sq. mm+1x6 Sq. mm earth Wire	10	M	324.00	3,240.00	1.7.4
	S/F Piano type switch/ socket :					
3	Supplying and fixing following piano switch/ socket on the					
	5/6 amps switch	3	Each	34.00	102.00	1.23.1
	Total of DSR 2016 Items (IN Rs)				**7,163.00**	
2(iii)c	***Market Rate Items***					
	LIGHT FITTINGS AND FIXTURES					
1	.Supply & Installation, of .Philips Astra Line 1x 20 W 4 Ft Straight Linear LED Tube Light or equivalent complete with all accessories etc	4	No.	750.00	3,000.00	NSR.
	Total of Market Rate Items (In Rs)				**3,000.00**	