Hindustan Prefab Limited

Jangpura, New Delhi - 14

CONSTRUCTION OF ESIC SUPER SPECIALTY HOSPITAL AT VARANASI COST ESTIMATE OF TRACK AND CURTAIN

NIT NO: HPL/PM/TC/ESIC/Varanasi/2018-19/82 Dated: 17.12.2018

Financial Bid

Name of the Agency : M/s .

S.No.	Description Of Item	Quantity	Unit	Rate (in Rs.)	Amount (in Rs.)
	CURTAIN TRACKS				
1	Providing and installation of Curtain Track V RAIL 4100-(including all accessories) strong functional and fully reversible profile confirming to HTM66, synthetic wall and ceiling brackets complying with the European NEN 1010 standards, made of aluminum 606035- T6 –F2. Shape and size tolerance in accordance with DIN 17615. White powder coating color RAL 9010, in accordance with Quali coat standard. Runner/Glider hooks made of nylon 6.6 with SS 304 grade hooks. Profile weight must be 394 g/m. The system is such that if required can be mounted with ANTI- LIGATURE load release components, to provide a controlled system collapse as per NHS guidelines, this can be installed by suspension hanger / wall support / ceiling support LIST OF APPROVED MAKES - WINDOW TECHS / RV SALES / DHEERAJ CRAFT	1166.03	RM		0.00
	CUBICAL PRIVACY CURTAINS				
2	Providing and installation of Curtains fabric to comply with many safety protocols it must be stain retardant and has a coating of antimicrobial and fire retardancy effect, must be certified according to international standards, must be certified by Indian Govt approved laboratories. it has to contributes to the reduction of transferring bacteria, help in increasing/improvement of hygienic standards provide greater safety against infection. No need of sterilization after wash. The antibacterial component facilitates in reducing the growth of fungi, moulds and mildew that can develop in any type of an indoor environment. Effective after 100 washes and, it must be Oeko Tex certified, LIST OF APPROVED MAKES - WINDOW TECHS / RV SALES / DHEERAJ CRAFT	2448.66	SQM		0.00
	IV BAG HOLDER				
3	Providing and installation of Bag Holder. It must suspend from EZE lock I.V Carriage, Made from Stainless Steel for hygiene, Use with Ultra Cube Track OR with Optitrac to suspend track from hard ceiling for support. Size Open length 41.5" Closed length 27" LIST OF APPROVED MAKES - WINDOW TECHS / RV SALES / DHEERAJ CRAFT	150	sets		0.00
	WALL GUARDS				
4	Providing and installation of Wall Guards. The system fixed to brick wall at 900mm center high from finished floor level comprising continuous aluminum rail retainer, 2 impact absorbing strips, end cap and high impact vinyl acrylic snap-on textured surface cover. The wall guard must be 152 mm wide, as specified by the client, must have 2mm thick aluminum retainer, must have 2 mm thick scratch and stain resistance rigid vinyl cover, should be coated with antifungal and antibacterial chemical. the system shall be designed to withstand impact and provides a cushioned surface with its integrated rubberized absorber, making it ideal for areas like high traffic corridors, loading bays and light cargo lifts. the vinyl cover should be fire retardant according to the norms and should have test certificates according to IEC- 62321-2008. it must be according to ROHS compliances. The material should come the ROHS certification from govt approved lab. It must not be having any toxic metals and it should have testing certificate according to IEC-62321-2008. Texture to provide an anti-slip surface, it should have adjustable end cap, corner joint and adaptor plate. aluminum retainer should be in mill finish and fabricated from 6063-T5 alloy. LIST OF APPROVED MAKES - WINDOW TECHS / RV SALES / DHEERAJ CRAFT	2500	R.Mtr		0.00
	CORNER GUARDS				
5	Providing and installation of Corner Guards. The system fixed to brick wall at the corner from finished floor level. Adjustable end cap. High impact vinyl acrylic snap-on matt finished. "50mm wide x 10mm thickness x 900mm length ". The corner guard must be 50 mm * 50 mm, as specified the client in size with aluminum retainer and rigid vinyl, must have 2mm thick aluminum retainer, must have 2 mm thick scratch and stain resistance rigid vinyl cover, should be coated with antifungal and antibacterial chemical. the system shall be designed to withstand impact. making it ideal for areas like high traffic corridors and corners. the vinyl cover should be fire retardant according to the norms and should have test certificates of that. it must be according to ROHS compliances. The material should come the ROHS certification from govt approved lab. texture to provide an anti-slip surface, it should have adjustable end cap. aluminum retainer should be in mill finish and fabricated from 6063-T5 alloy. LIST OF APPROVED MAKES - WINDOW TECHS / RV SALES / DHEERAJ CRAFT	500	R.Mtr		0.00
	Total Amount (in Rs.)				0.00