HINDUSTAN PREFAB LIMITED
JANGPURA, NEW DELHI : 14

NAME OF WORK: Supplying, Installation, Testing & Commissioning of CSSD & TSSU equipment's for 150 bedded ESIC Hospital at Pandeypur, Varanasi, Uttar Pradesh.

BILL OF QUANTITY (CSSD)

S.NO.	ITEM DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
1.00	Supply, installation, Testing & Commissioing of HORIZONTAL RECTANGULAR HIGH PRESSURE DOUBLE DOOR STEAM AUTOCLAVE WITH HINGE DOOR The chamber size of 600 X 600 X 1200 mm approx would be constructed of ASIS 316 stainless steel and jacket would be constructed of boiler quality steel approx capacity of 432 litre.	2.00	Each		
2.00	Supply, Installation, Testing & Commissioing of Stainless Steel 316 carriage suitable for Rectangular Sterilizer	2.00	Each		
3.00	Supply, Installation, Testing & Commissioing of Stainless Steel 304 Trolley suitable for above carriage	4.00	Each		
4.00	Supply, Installation, Testing & Commissioing of WASHER DISINFECTOR CAP. 250 TO 275 LTRS.	1.00	Each		
5.00	Supply, Installation, Testing & Commissioing of DRYING / HEATING CABINET CAP. 250 TO 275 LTRS.	1.00	Each		
6.00	Supply, Installation, Testing & Commissioing of ULTRASONIC CLEANER CAP. 30 LTRS.	1.00	Each		
7.00	Supply, Installation, Testing & Commissioingof GAUZE CUTTING MACHINE SIZE 1500 X 650 X 850MM	1.00	Each		
8.00	Supply, Installation, Testing & Commissioing of SINGLE DISTILLED WATER STILL CAP. 20 LTRS., ELECT LOAD 15KWWS.	1.00	Each		
9.00	Supply, Installation, Testing & Commissioing of S.S.STORAGE TANK FOR DISTILLED WATER CAP. 120 LTRS., ELEC LOAD 6 KWS.	1.00	Each		
10.00	Supply, Installation, Testing & Commissioingof WASH STATION WITH DOUBLE SINK SIZE : 2400X 900 X 650MM	2.00	Each		
11.00	Supply, Installation, Testing & Commissioing of S.S.PACKING & CONTROL TABLE WITH TWO SHELVES SIZE : 2000 X 1400 X 1400MM	2.00	Each		

S.NO.	ITEM DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
12.00	Supply, Installation, Testing & Commissioingof STORAGE RACKS	6.00	Each		
	SIZE : 1830 X 535 X 1835MM				
13.00	Supply, Installation, Testing & Commissioing of S.S.WORK TABLE	3.00	Each		
	SIZE : 1500 X 610 X 890MM				
14.00	Supply, Installation, Testing & Commissioing of HEAT SEALER-ROTARY TYPE	1.00	Each		
15.00	Supply, Installation, Testing & Commissioingof SPRAY GUN RINSER FOR WATER	1.00	Each		
16.00	Supply, installation testing commissioing of SPRAY GUN RINSER FOR AIR	1.00	Each		
17.00	Supply, Installation, Testing & Commissioing of PASS BOX	1.00	Each		
	SIZE : 600 X 600 X 600MM				
18.00	Supply, Installation, Testing & Commissioingof S.S.TABLE TROLLEY WITH TWO SHELVES	4.00	Each		
	SIZE : 1080 X 530 X 800MM				
	TABLE TROLLEY USE IN THE STERILE GOODS STORE.				
	TOTAL AMOUNT				

NOTE :

1 The quoted rates of the bidders will be inclusive of all the taxes including GST, Transportation, Loading & Unloading, Installation, Testing & Comissioning of the equipments in all respect. Nothing extra will be payable on any account. For Testing & Commissioning of equipments, arrangement of water & electricity will be made by the contractor at his own.

2 All the equipments should confirm to the technical specifications given in the tender document. However, if any of the specifications is missing or not given in the tender document, the equipment should confirm to the best specifications of the trade & equipment duly approved by the Engineer-in-Charge.