

Hindustan Prefab Limited

Jangpura, New Delhi - 14

Name of work: Providing and Fixing Signage for 150 Bedded ESIC Hospital at Pandeypur, Varanasi (UP).

NIT NO: HPL/PM/TC/ESIC/Varanasi/2018-19/114 Dated: 11/03/2019

Financial Bid

Name of the Agency : M/s.

S.No			Qty	Unit	Rate (in Rs.)	Amount (in Rs.)
1	N.S	Information Sign				
		Providing and fixing Readymade information signs for service areas in stainless stell finish (Grade 304, 1.5-2 mm thick) with information embossed or cut out with appropriate lettering/Pictograms / Complete as per the attached referance images, Lettering font, size and content subject to final approval of the architect in charge				
1.1	(a)	Service Areas Size of Plate 6"X6" with rounded Glass	24.00	Each		-
1.2	(b)	Functional Areas Size of Plate 12" X3".	24.00	Each		-
2	N.S	Rooms's Name Plates				
		Providing and fixing Room Plates on glass/wooden Partitions/Glass doors as per the approved location, Size of the SS Plate (Grade 304, 1.5-2 mm thick)- 6" X 6" with acrylic black rimming sliding room occupany indicator, lettering to be embossed / etched complete as per the attached image. Font and final deisgn subject to final approval of the architctec in charge.	631.00	Each		-
3	N.S	Direction Signages				
		Providing and Fixing Direction signages on toughened glass sheet. Content to be displayed using plotter cut lettering on one side of the sheet, with additional taping to achieve a uniform background . Lettering font size , Color and content subject to final approval of the architect in charge, Cost to include mounting of Glass sheets using SS Studs on masonry wall surface or suspending the sheets using ss rods from the ceiling.				
3.1	(a)	Glass sheet size 18" x 30"	57.00	Each		-
3.2	(b)	Glass sheet size 28" x 42"	15.00	Each		-
4	NS	Fire Exit Signs				
		Providing and installation Fire exit sign ceiling hanged, Led Emergency with Ni-cd Battery backup capable of emergancy backup of 2Hr. Complete with hanging accessoires to the statisfaction of Engineer-in-Charge.	30.00	Each		-
		Total Signages work				-