

Name of work: Balance work in Construction of RURAL SELF EMPLOYEMENT TRAINING INSTITUTE (RSETI)Building for PNB-CRDT at Kullu, Himachal Pradesh (at Risk & Cost)

ROAD WORKS

As per BOQ

SL.NO.	Item No in DSR-14	DESCRIPTION	UNIT	RATE	Total Qty as per BOQ (M/s SKP Buildcon Pvt. Ltd. or approved erlier	Qty Executed by M/s SKP Buildcon Pvt. Ltd.	Balance Qty to be Executed	Amount
1.0		SITE DEVELOPMENT AND EARTH WORK						
		Surface Dressing						
1.1	2.28	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m.						
1.1.1	2.28.1	All kinds of soil	Sqm	8.51	177.00		177.00	1,506.38
2.0		CONCRETE & FLOORING WORK					-	-
							-	-
		(Rates for all cement concrete items plain and reinforced described below shall include work from Basement Level to top of last roof including					-	-
							-	-
		Plain cement concrete					-	-
2.1	4.19	Providing and laying in position ready mixed plain cement concrete, using fly ash and cement content as per approved design mix and manufactured in fully automatic batching plant					-	-
		Note :					-	-
		(1) Excess/less cement used than specified in this item is payable/ recoverable separately.					-	-
		(2) Fly ash conforming to grade I of IS 3812 (Part-1) only be used as part replacement of OPC as per IS : 456. Uniform blending with cement is to be ensured in accordance with clauses 5.2 and 5.2.1 of IS: 456 -2000 in the items of BMC and RMC.					-	-
2.1.1	4.19.1	All works upto plinth level :					-	-
2.1.1.a	4.19.1.1	M-15 grade plain cement concrete (cement content considered @ 240 kg/cum)	cum	6,049.09	18.00		18.00	108,883.62
2.1.1.b	4.19.1.2	M-10 grade plain cement concrete (cement content considered @ 220 kg/cum)	cum				-	-
2.2		CC PAVERS					-	-
		Providing and laying factory made chamfered edge Cement Concrete paver blocks of required strength, thickness & size/shape, made by table					-	-
2.2.1	(a)	80 mm thick c.c. paver block of M-30 grade with approved color design and pattern.	Sqm	620.27	177.00		177.00	109,787.79
							-	-
							-	-
		Total carried over to summary				-		220,177.00